



FURNITURE ARRANGEMENT PLAN

PLAN SHOWING PROPOSED BANK PREMISES ON GROUND FLOOR FOR
CENTRAL BANK OF INDIA, CHAPRASHIPURA BRANCH, AMRAVATI.
TQ. & DIST. - AMRAVATI.

ASHISH V. JOSHI
ENGINEERS . PLANNERS . VALUERS
NAWATHE NAGAR, AMRAVATI

DETAILED ESTIMATE FOR BANKING INTERIOR FOR CENTRAL BANK OF INDIA,
CHAPRASHIPURA BRANCH, AMRAVATI, TQ. & DIST. - AMRAVATI.

DETAILED ABSTRACT

Item No.	Discription	Quantity	Rate	Unit	Amount
1	Preparation of Clerical counters @ 4'0" length, 2'6" wide & 2'6" ht. in 19 mm th. marine ply at top & sides & 12 mm th. for drawers & front aprons with 1 mm th. laminate on top & front visible side/ with all fittings, keyboards to each counter with channel, drawer handles & inner side polish etc. complete. (For 1 Clerical Counter & 1 Cash cabins)	8.00		RFT	
2	Preparation of top & side part of cash cabin in T.W rafters frame 2"x2" at 2'6" c/c at side, front & back side covered with 8 mm th ply up to 3'0" ht 8 mm th. glass from 3'0" to 7'0" ht, with top part by Aluminium mesh supported by T. W. rafters with all fittings etc. complete.	82.00		SFT	
3	Providing & fixing 12 mm toughened glass on front side of Cash cabin & Counters with all fittings etc. complete.	29.00		SFT	
4	Providing Low height Cabinates in 19 mm th. marine ply at top, bottom & sides with 12 mm th. shelvings with 1 mm th. laminate with all bidding & fittings etc (Size 36"x15"x30" ht.) .	3.00		NO.	
5	Providing Full ht. half ply & half glass partition to Server Room & branch Manager Cabin in 2" X 2" T.W. Section frame @ 2'6" C/C with 6 mm th. ply on both sides with 1 mm th. laminate & glass with all bidding & fittings etc.	363.50		SFT	
6	Providing & Preparing Branch Manager Table of size 5' X 2'3" in 19 mm marine ply at support & top & 12 mm th. ply for front & drawers with 1 mm th. laminate on visible side of Table & top with keyboard, bidding & fittings etc. a. Branch Manager Table (5'0" Length) b. Officer Table (4'0" Length) c. Server Table (6'0" Length)	1.00 3.00 1.00		NO. NO. NO.	

.2.

Item No.	Discription	Quantity	Rate	Unit	Amount
7	Providing & fitting Door closure of approved quality.	4.00		NO.	
8	Providing & fitting Mortice Lock of approved quality.	4.00		NO.	
9	Providing & fixing False ceiling of Gypsum decorative boards 15 to 20 mm th. of size 24" X 24" with all necessary scaffoldings, frame work of Al. angle 25 x 25 x 4 mm at 60 cm c/c to vertically & horizontally for sheet fitting with all finishing etc. complete.	585.00		SFT	
Total Amount					