

S. No.	Description of Item	Unit	Quantity	Rate	Amount
(A)	<b>CIVIL / INTERIOR WORKS</b>				
<b>1</b>	<b>DISMANTLING &amp; DISPOSAL</b>				
	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead				
	Dismantling CI pipes including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes & lead at site within 50 metre lead as per direction of Engineer-in-charge				
	Dismantling tile work in floors and walls laid in cement mortar including stacking material within 50 metres lead				
	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge				
	Dismantling electric fixtures, switch, sockets, internal wires, DBs, MCBs, MS pipes, switch board etc. including stacking material within 50 metres lead				
	Dismantling plumbing/sanitary fixtures, taps, chinawares, WC, mirror, valves, tanks etc. including stacking material within 50 metres lead				
	Disposal of building rubbish/ malba/ similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved				
	Dismantling and demolishing and Buy Back of serviceable material				
	The contractor shall conform to the provisions of all local bye- laws and acts relating to the dismantling and demolition work and to regulations etc. of the government and local authorities including cordoning off the property from the neighbouring properties with proper arrangement etc. to avoid dust, noise to the occupants of neighbouring flats etc.				
	<b>Total payable to owner after accounting for cost of demolition and disposing of the debris and other unserviceable material to the municipal ground carried over to GRAND SUMMARY OF BOQ</b>	<b>L.S.</b>	<b>-1.00</b>		

PRICE BID (ONLY THROUGH ONLINE MODE)

2	Providing and laying in position cement concrete of specified grade with water proofing material including the cost of centring and shuttering				
	1:4:8 mix -1 Cement: 4Coarse sand: 8 Graded stone aggregate mm 40 mm nominal size	Cum	0.45		
3	Providing and laying in position specified grade of reinforced cement concrete including the cost of centring, shuttering, finishing and reinforced bars				
	1 : 1.5 : 3 ( 1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size ) :	Cum	0.45		
4	Half brick masonry with Fly ash based bricks of class designation 7.5 in the superstructure				
	cement mortar 1:4 ( 1cement :4 Coarse sand)	Sqm	2.25		
5	Providing wood work in frames of doors, windows, clerestory windows , Handrails and other frames, wrought framed and fixed in position				
	Second class teak wood	cum	0.15		
6	Providing and fixing ISI marked flush door shutters conforming to IS 2202 (Part I) non-decorative, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters :				
	35 mm thk including ISI marked Stainless Steel butt hinges with necessary Screws	Sqm	4.25		
7	Providing and fixing upto 4mm thick decorative veneer laid in approved pattern on existing door shutters complete in all respect				
	Natural Teak ( century/equivalent approved )	Sqm	4.25		
8	Extra for providing and fixing lipping with 2nd class teak wood battens minimum 25mm minimum depth on all edges of flush door shutters ( over all area of door shutter to be measured )	Sqm	4.25		
9	Providing and fixing of 1 mm minimum thickness premium range laminate in wood grains shades with textured surface laid in approved pattern on existing door shutters etc. complete in all respect as per directions and approval ( Sunmica /equivalent approved )	Sqm	19.50		
10	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs				

	and priming coat on unexposed surface etc. complete :				
	2nd class teak wood				
	50x12 mm	<b>Rm</b>	12.00		
<b>11</b>	Providing and fixing factory made uPVC glazed/wire mesh windows/doors comprising of lead free uPVC multi-chambered frame, sash and mullion/coupler (where ever required) extruded profiles having minimum wall thickness of 1.70 mm for Series R1 and R2 profiles and 2.10 mm for Series R3 and R4 profiles conforming to EN: 12608 in any shape, colour and design duly reinforced with galvanized mild steel section made of required shape & size as per CPWD Specification, uPVC extruded glazing beads, interlocks and Inline sash adaptor (where ever required) of appropriate dimension, EPDM gasket, hardware, SS 304 grade fasteners of minimum 8 mm dia with countersunk head, comprising of matching polyamide PA6 grade sleeve for fixing frame to finished wall as per IS 1367 : Part 1 to 14, plastic packers, plastic caps and necessary stainless steel screws etc. Profile of frame, sash & mullion (if required) shall be mitred cut and fusion welded/mechanically jointed duly sealed at all corners, including drilling of holes for fixing hardware and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of approved size and quality, all complete as per approved drawing conforming to CPWD specification & direction of Engineer-in-Charge. Section of steel reinforcement and cross sections of uPVC profiles to be as per design approved by Engineer-in-Charge. Wire mesh / Glazing of plain/ toughened/ laminated/ double glass unit with / without high performance coatings as per design requirements and conforming to IS: 3548 & IS: 16231 shall be paid separately.				
<b>a</b>	Two track two panels sliding window with two glazed & one wire mesh panels Aluminium channel for roller track, wool pile, nylon rollers with SS 304 body. Using R3 series with frame (55mm & above) x (40mm & above) & sash (30mm & above) x (55mm & above) with zinc alloy (zamak) powder coated handle on every panel along with multipoint locking system (Height upto 1.8 metre).	<b>Sqm</b>	1.20		
<b>b</b>	Fixed window / ventilator without mullion /				

	transom.				
	Using R2 series with frame (39mm & above) x (39mm & above). (Height up to 1.20 metre)	<b>Sqm</b>	0.80		
12	Providing and fixing low ht factory made modular kitchen cabinets in modular type knockable cabinet boxes under counter storage unit for Kitchen upto 600 deep in 17mm or more thick. HDHMR / EDHMR board construction with 7mm or thicker ply backing. The vertical divisions shall be as per the drawing/details at spacing with 17mm or more HDHMR / EDHMR board not more than 450 mm. All internal surface of storage counter shall be in 1mm thick white Laminate finish .All edges will finished with 18mm wide 2mm thick PVC edge banding. All the shutters shall be made in 19mm thk. BWP Ply with 1.5 mm thick premium acrylic sheet on exterior side and 1 mm thick laminate on interior sides auto closing hinges ( hettich make ) and upto 4 mm thk margins polished in matching shade. All shutters shall have tubular Kich make CHR104C equivalent approved make handles and these shall be fixed with auto (soft) closing hinges. (The shutter will include fixing with automatic hinges of Hettich make). Upto one shelf per module, should be supported on approved quality SS pins and shall be adjustable for different heights as per requirements. All hinges shall be soft auto closing type having capacity to take load of the structure.	<b>Sqm.</b>	3.25		
13	Providing and fixing factory made modular kitchen cabinets in modular type knockable cabinet boxes over counter storage unit upto 375mm depth and 700mm high made out of 17 mm or more HDHMR boards for verticals, top, bottom, and intermediate vertical partitions @600 c/c or part thereof and backing of 6 mm thk. HDHMR ply. The inside (interior) of storage to be finished with 1mm thick laminate and exterior sides is to be finished with 1.5mm premium acrylic complete in all respects as per design. All edges will finish with 18mm wide 2mm thick PVC edge banding. Upto one shelf per module should be supported on approved quality SS pins and shall be adjustable for different heights as per requirements. All hinges shall be soft auto closing type having capacity to take load of the structure.	<b>Sqm.</b>	2.10		

PRICE BID (ONLY THROUGH ONLINE MODE)

<b>14</b>	Wardrobe : Providing and fixing upto 600mm deep and upto ceiling high storage unit made out of 17mm or more HDHMR boards for verticals, top, bottom, and intermediate vertical partitions @ 900 c/c or part thereof and backing of 6 mm th. HDHMR ply. The inside, top & exposed sides of storage to be finished with laminate and complete in all respects as per design.				
	Shutters shall be in 19 mm BWP grade block board with teak wood lipping all -around. The front & back to be finished with 1 mm thick laminate. Front will be wood color premium laminate and inside will be 1mm thk white laminate				
	Shelves are made of 17mm or more HDHMR boards with teak wood lipping and fixed @ 600 mm c/c supported on heavy duty S.S pins or fixed to sides as per directions. The teak wood lipping shall be enamel painted. Wardrobe shall have four no drawers for each wardrobe module width up to 900 mm as per drawing and shall moveable on channels which shall be paid extra. Telescopic channels shall be paid extra for each wardrobe				
	Locks shall be Godrej make universal drawer/ cupboard lock (model no 5041) dead lock with S.S key- master key for groups as required.				
	Handles shall be Kich or equivalent approved make AIAI 316 grade 96 mm long 12 mm dia. for each shutter.	<b>Sqm.</b>	3.55		
<b>15</b>	Providing fixing telescopic channels of following length with necessary screws etc. complete as per directions				
<b>a</b>	450 mm	<b>Nos</b>	8.00		
<b>b</b>	550 mm	<b>Nos</b>	8.00		
<b>16</b>	Providing and fixing following stainless factory made steel kitchen/wardrobe over the counter /under the counter accessories of Kaff/Hettich make or other equivalent approved brand including necessary channels, screw etc complete in all respect required to complete the modular kitchen ALL drawers shall be of type tandem innotech hettich				
<b>a</b>	Dish Drainer set	<b>Nos</b>	1.00		
<b>b</b>	Cutlery Basket	<b>Nos</b>	2.00		
<b>c</b>	Pull out trolley	<b>Nos</b>	4.00		
<b>d</b>	Pull out multipurpose basket	<b>Nos</b>	2.00		
<b>17</b>	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc.				

**PRICE BID (ONLY THROUGH ONLINE MODE)**

	complete :				
<b>a</b>	250x10 mm	<b>each</b>	2.00		
<b>b</b>	150x10 mm	<b>each</b>	2.00		
<b>c</b>	100x10 mm	<b>each</b>	2.00		
<b>18</b>	Providing and Fixing following types of Dorset equivalent approved handles /locks etc. system complete in all respect				
<b>a</b>	Providing and fixing chromium plated brass 100 mm mortise latch and lock with 6 levers and a pair of lever handles of approved quality with necessary screws etc. complete	<b>each</b>	4.00		
<b>b</b>	Door Chain	<b>each</b>	1.00		
<b>c</b>	Eve view model	<b>each</b>	1.00		
<b>d</b>	Pull Handle pair	<b>each</b>	2.00		
<b>19</b>	Providing and fixing stainless steel (Grade- 304) railing /gates etc. made of hollow tubes, channels, plates etc. including welding, grinding, buffing, polishing and making curvature(wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i.e. fixing the railing /gates with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc. of required size, on the top of the floor or the side of waist slab with suitable arrangement as per the approval of Engineer- incharge, (For payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	<b>kg</b>	45.00		
<b>20</b>	Providing and fixing expansion hold fasteners on C.C./R.C.C/Brick masonry surface backing including drilling necessary holes and the cost of bolt etc. complete :				
	Wedge expansion type				
<b>a</b>	Fastener with threaded dia. 10mm.	<b>Nos</b>	18.00		
<b>21</b>	Providing & fixing fly proof wire gauze to windows, clerestory windows & doors with nuts & bolts complete				
	Stainless steel (grade 304) wire gauze of 0.5 mm dia. wire and 1.4 mm aperture on both sides	<b>sqm</b>	2.00		
<b>22</b>	Providing and fixing glazing in UPVC door, window, ventilator shutters etc. complete as per the architectural drawings and the directions of engineer -in-charge ( (Area of opening for glass panes excluding portion inside rebate shall be				

PRICE BID (ONLY THROUGH ONLINE MODE)

	measured):				
<b>i</b>	With float glass panes of 4.0 mm thickness	<b>Sqm</b>	2.00		
<b>ii.</b>	With float glass panes of 5.0 mm thickness	<b>Sqm</b>	2.00		
<b>23</b>	Providing and laying premium double charged vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and confirming to IS:15622 of approved make in all colours and shades, laid on 20 mm cement mortar 1:4 ( 1cement :4 coarse sand ) jointing with grey cement slurry@ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete.				
	Size of tile 600 X 600 mm	<b>sqm</b>	101.25		
<b>24</b>	Providing and laying rectified Glazed Ceramic floor tiles 300x300 mm or more (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in all colours, shades, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand) including pointing the joints with white cement and matching pigments etc., complete.	<b>sqm</b>	7.75		
<b>25</b>	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	<b>sqm</b>	34.25		
<b>26</b>	Providing and laying any texture /digital tiles in skirting, risers of steps and dado on 12mm thick cement plaster 1:3(1 cement: 3 coarse sand) and jointed with white cement slurry and matching pigment etc.	<b>Sqm</b>	6		
<b>27</b>	Providing and fixing 20 mm thick mirror polished, pre moulded, pre polished machine cut granite for kitchen platform, vanity counters facias and similar locations of required size of approved shade , colour and texture laid over 20 mm thick base cement mortar 1 : 4 ( 1 cement : 4 coarse sand ) with joints treated with white cement , mixed with matching pigment , epoxy touch ups , including rubbing , curing moulding and polishing to edge to give high gloss finish etc. complete.				



**PRICE BID (ONLY THROUGH ONLINE MODE)**

<b>a</b>	AGL Quartz of any colour and shade (Basic price of stone upto Rs 4000/- per Sq.M.)				
<b>i</b>	all levels : upto 0.50 sqm slab area	<b>Sqm</b>	1.00		
<b>ii</b>	all levels : above 0.50 sqm slab area	<b>Sqm</b>	1.00		
<b>28</b>	Extra for providing opening of required size & shape for wash basin/kitchen sink in kitchen platform, vanity counter and similar location in marble/Granite/stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	<b>each</b>	6.00		
<b>29</b>	Extra for providing edge moulding to 18 mm thick Marble stone counters, vanities, steps etc. including machine polishing to edge to give high gloss finish etc. complete as per approved design by Engineer-in-charge.				
<b>a</b>	Granite work	<b>Metre</b>	6.00		
<b>30</b>	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement :4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge :				
	Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	<b>Sqm</b>	1.00		
<b>31</b>	Rates of external plaster are for height upto 3.5 m from floor level unless otherwise specified				
	12 mm cement plaster of mix:				
	1:4(1cement:4 fine sand)	<b>Sqm</b>	4.00		
<b>32</b>	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	<b>sqm</b>	300.00		
<b>33</b>	Wall painting with Asian Premium plastic emulsion paint or equivalent including coat of primer of approved brand and manufacture to give an even shade:				
	Two or more coats on new work	<b>sqm</b>	280.00		



34	Distempering with 1st quality acrylic distemper ( ready mixed) having VOC (Volatile Organic Compound) content less than 50 gm/litre of approved brand and manufacturer and of required shade and colour all complete to achieve an even shade and colour				
	Two or more coats over and including water thinnable primer having VOC content less than 50 gm/litre	Sqm	125.00		
35	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:				
	Two or more coats over an under coat of suitable shade with ordinary paint of approved brand and manufacture	sqm	16.00		
36	Providing and fixing in position approved design Heavy duty Stainless Steel curtain rods for doors and windows, 25 mm dia. 16 guage thick, with matching approved design brackets at both sides and curtain supports at intermediate positions where length of span exceeds 1.5 m as directed by Bank's Engineer. The rate quoted shall include the cost of materials, necessary fittings and fixtures, transportation of materials, labour charges, etc. complete.	m	16.00		
37	Finishing walls with premium Acrylic Smooth exterior paint with silicone additives of required shade				
	New work (Two or more coats applied @1.43 ltr/10sqm.over and including base coat of water proofing cement paint applied @ 2.20 kg/ 10 sqm). ( Asian Ultima or equivalent approved )	Sqm	20.00		
(B)	<b><u>ELECTRICAL WORK</u></b>				
38	<b>DISTRIBUTION BOARDS :</b>				
	Supply and installation of following 6 way TPN DB double door type distribution boards fabricated out of 16 SWG, CRCA sheet steel recessed in wall or surface mounted complete				
	LPDB				
	Incoming:				
	One (1) 63 Amp TPN MCB 10 KA as incomer				
	Outgoing:				
	Eighteen (18) nos 6/10/16A/25/32 SP MCBs, 10 KA.	Set	1.00		

<b>39</b>	<b>Point Wiring :</b>				
	Supplying, wiring, testing and commissioning for lights, ceiling fans, exhaust fans and 6 A socket outlets (where 6 A socket connected to lighting circuit) using 1.5 Sqmm stranded copper, 1100 volts grade, PVC insulated wires drawn through, PVC conduit including laying of conduits in a concealed/ surface manner using necessary conduit accessories, junction boxes, switch outlet boxes, switch plates, bends, collars, clamps, 6/16 A, one way/ Two way switches, fan regulator boxes, etc. shall be flush mounted in brick wall or on the surface of wall for surface installation as required. [ Switch Plates, Switches, sockets boxes shall be Legrand or equivalent pre-approved by Bank]				
	The rate for point wiring (using 2 Nos. 1.5 Sqmm 1100 V grade PVC insulated copper wires for phase & 1 No. 1.5 Sq.mm copper conductor wire for earth) shall include the circuit wiring (using 2.5 Sqmm, 1100 V grade PVC insulated copper wires) from the DB up to the first light/fan/6 A convenience socket outlet control switch on wards to light/fan then the looping between switches /lights /fans /6 A socket etc. The circuit wiring will not be paid separately. However where the lights are controlled directly from DB without local control switch, the quoted rates shall not include cost of switches/MCB etc.				
	Also the rate shall include earthing of each light, fan outlet boxes, switches, switch plates, switch control boxes, 6A sockets using 1.5 Sqmm copper, PVC insulated wires and flexible conduit from junction box to the fitting as required.				
<b>a)</b>	Primary light point i.e. one light controlled by one switch or first light in the group in which more than one lights are controlled by one switch.	<b>Nos.</b>	18.00		
<b>b)</b>	Primary light point directly controlled by existing MCB in DB.	<b>Nos.</b>	2.00		
<b>c)</b>	Secondary light points ( Looped light points from Primary light points)	<b>Nos.</b>	22.00		
<b>d)</b>	Light points controlled by 2 Nos 2 way switch.		2.00		
<b>e)</b>	One 6 Amps, 2/3 pin switched socket outlet controlled by one 6 Amps switch.	<b>Nos.</b>	2.00		
<b>f)</b>	Additional 6Amps switched socket outlet to be fixed to adjacent to above item in same box.	<b>Nos.</b>	2.00		
<b>g)</b>	Exhaust fan point controlled by a 6A switch on the switch board and 6 A socket outlet near exhaust fan.	<b>Nos.</b>	4.00		
<b>k)</b>	Ceiling fan point controlled by a 6A switch on the switch board and stepped fan regulator.	<b>Nos.</b>	5.00		

**PRICE BID (ONLY THROUGH ONLINE MODE)**

<b>40</b>	Wiring for 6/16 Amp power outlet with 4 Sqmm PVC insulated stranded copper conductor wires in recessed/surface PVC conduit including cutting/filling chases, providing conduit with conduit accessories, saddles supply and fixing of 6 pin 6/16 Amps shuttered switched socket with internal wiring in G.I. box, earthing of 3rd pin with PVC insulated, green colour 2.5 Sq.mm copper wire, complete with all accessories as required. (Not more than two outlets shall be wired in one circuit).	<b>Nos.</b>	12.00		
<b>41</b>	Supply and drawing of following sizes of PVC insulated stranded copper conductor wires of 1100 Volts grade in existing conduit including connection/termination etc. as required.				
	4x10+1x6 Sqmm	<b>RM</b>	15.00		
<b>42</b>	<b>LIGHTING FIXTURES:</b>				
	Supply, Assembling, installation, testing & commissioning of following type of light fixtures and fans. All fixtures shall be provided with power factor improvement capacitors, electronic control gear & lamps as per requirements and installation arrangement using proper support etc. complete as required.				
<b>a</b>	Wall bracket 9-18 W LED Lamp (Basic cost: ₹900/-pc)	<b>Nos.</b>	6.00		
<b>b</b>	Surface Module 12 - 18 w Down lighter	<b>Nos.</b>	6.00		
<b>c</b>	T5 LED Batten 20 W	<b>Nos.</b>	16.00		
<b>d</b>	225mm dia. 900 rpm exhaust fan with louver shutter	<b>Nos.</b>	4.00		
<b>e</b>	1200mm sweep BLDC 5 star ceiling fan	<b>Nos.</b>	5.00		
<b>43</b>	<b>AC POINTS</b>				
	Supply, Installation, Testing and commissioning of surface / recess mounting modular 25 A modular starter unit comprising of 25 A starter, 25 A socket with 25 A plug including wiring with 2 X 4.0 sq mm + 1 X 2.5 sq mm PVC insulated copper conductor single core multi stranded wire in MMS grade-PVC conduit with conduit accessories like bend, junction box etc. on surface / recessed manner etc. (Wiring from D.B. / Source to Board/destination) and making good all the damages, painting, cleaning the site etc. complete as required as per site requirement and as directed.	<b>Nos.</b>	5.00		
<b>(C)</b>	<b><u>PLUMBING / SANITARY WORK</u></b>				

PRICE BID (ONLY THROUGH ONLINE MODE)

<b>44</b>	Providing and fixing white vitreous china extended <b>wall hung Water Closet</b> of size 380x650x730 mm of approved shape, with PP soft close seat cover, hinges, Accessories set Including fitting, nuts, bolts and gasket etc. complete.	<b>Each</b>	2.00		
<b>45</b>	Providing and fixing Single piece slim concealed flushing cistern including floor mounting frame , installation Kit and "S" type drain pipe or approved equivalent including providing and fixing flushing plate with all fittings and fixtures complete to connect to W.C.	<b>Each</b>	2.00		
<b>46</b>	Providing and fixing table top type vitreous china wash basin of 520x360X125 mm size for with specially fabricated brackets/bolts, painted white, 32mm C.P. waste, 32mm dia. cast brass bottle trap and connection pipe to wall with C.P. wall flange and rubber adopter for waste connection, complete including cutting and making good the walls, wherever required.	<b>Each</b>	3.00		
<b>47</b>	Providing and fixing stainless steel A ISI 304 (18/8) kitchen sink as per I.S.13983 with C.I. Brackets, stainless steel plug 40mm including painting of fittings and brackets cutting and making good the walls wherever required.				
	Kitchen sink with drain board				
	510x1040 mm bowl depth 250mm	<b>Each</b>	1.00		
<b>48</b>	Providing and fixing towel ring with concealed fittings arrangement of approved quality and colour, weighing not less than 88gms.	<b>Each</b>	3.00		
<b>49</b>	Folding towel rack with total length of minm. 60 cm L x 24 cm W x 18 cm H, weighing not less than 1.2 kg which can easily store 4 towels side by side and 4-5 hooks for hanging cloths and a towel bar for drying purpose	<b>Each</b>	3.00		
<b>50</b>	Providing & fixing C.P brass Long Body bib cock of approved quality and weighing not less than 690gms.				
	15 mm nominal bore	<b>Each</b>	3.00		
<b>51</b>	Providing & fixing plasticised PVC connection pipe with brass unions				
	45 cm length				
	15 mm nominal bore	<b>Each</b>	6.00		

PRICE BID (ONLY THROUGH ONLINE MODE)

52	Providing and fixing C.P. brass angle valve 15mm dia. for basin mixer and geyser points of approved quality conforming to IS : 8931 .				
	15mm nominal bore	Each	8.00		
53	Providing & fixing PTMT/ABS liquid soap Dispenser of minm. 300ml capacity with concealed fitting arrangements.	Each	3.00		
54	Providing and fixing of CP Brass shower rose with 15 or 20 mm inlet:				
	100 mm diameter	Each	2.00		
55	Providing & fixing stop cock of approved quality and colour				
	Concealed Stop cock, 15mm nominal bore, 108mm long, weighing not less than 108gms.	Each	3.00		
56	Providing & fixing 600 x 450mm x 8mm bevelled edge mirror of superior glass (of approved quality, Saint Gobain or equivalent) complete with 6mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Each	3.00		
57	Providing and fixing Health faucet in PVC Flexible Tube with wall hook	Each	2.00		
58	Providing & Fixing High-flow Diverter for shower including all fittings and connections complete as required.				
	Concealed body for single lever hi-flow diverter	Each	2.00		
59	Providing and Fixing wall mounted <b>single lever sink mixer</b> with swinging spout complete, including cutting and making good the walls wherever required.	Each	1.00		
60	Providing and Fixing <b>Two way bib cock</b> complete, including cutting and making good the walls wherever required.	Each	3.00		
61	Providing & Fixing stainless steel 4 <b>peg holder</b> of approved design/pattern to hang clothes fixed to wooden cleats with C.P. brass screws.	Each	3.00		
62	Providing and fixing hot water vertical 5 star rated water <b>Geyser</b> of following capacities complete in all respect including cutting and making good the walls wherever required as per approval of engineer				

PRICE BID (ONLY THROUGH ONLINE MODE)

	in charge.				
	15 litre – Storage type	<b>Each</b>	2.00		
	3 litre – Instant type	<b>Each</b>	1.00		
<b>63</b>	Providing and fixing readymade glass corner shelf with SS railing (sides of 9-12 inch length) over the dado tiles without damaging the tiles. Including labour, rawl plugs, screws, etc. as per approval of engineer in charge.	<b>Each</b>	4.00		
<b>64</b>	Providing and Fixing wall mounted <b>Centre hole Basin mixer</b> with pop up waste system with 450mm long braided Hoses, including cutting and making good the walls wherever required.	<b>Each</b>	2.00		
<b>65</b>	Providing and Fixing wall mounted Single lever <b>tall body Basin mixer</b> with 180 mm Extension body fixed spout without pop up waste system with 650 mm long braided Hoses, including cutting and making good the walls wherever required.	<b>Each</b>	1.00		
<b>66</b>	Providing and fixing PTMT grating of approved quality and colour.				
	Circular type				
	125 mm nominal dia. with 25 mm waste hole.	<b>Each</b>	4.00		
<b>67</b>	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes having thermal stability for hot and cold water supply including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge.				
	<b>Concealed work including cutting chases and making good the walls etc.</b>				
<b>a)</b>	15mm nominal outer dia. pipes	<b>Metre</b>	12.00		
<b>b)</b>	20mm nominal outer dia. pipes	<b>Metre</b>	8.00		
<b>c)</b>	25 mm nominal outer dia. pipes	<b>Metre</b>	8.00		
<b>68</b>	Providing & fixing brass stop cock of approved quality.				
<b>a)</b>	15 mm nominal bore	<b>Each</b>	2.00		
<b>b)</b>	20 mm nominal bore	<b>Each</b>	2.00		
<b>69</b>	Providing & fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats				

**PRICE BID (ONLY THROUGH ONLINE MODE)**

	complete.				
	25mmdia nominal bore	<b>Each</b>	2.00		
<b>TOTAL AMOUNT =</b>					

**SUMMARY OF TOTAL WORKS**

<b>Description</b>	<b>Total Cost (in Rs.)</b>
A. Civil / Interior Works (point 1 -37)	
B. Electricals Works (point 38 – 43)	
C. Plumbing/Sanitary Works (point 44 – 69)	
Total Amount	₹
Total In Words:	

Above rates and amounts are excluding GST and GST as applicable shall be charged extra.

Date: \_\_\_\_\_

SIGNATURE OF TENDERER WITH RUBBER STAMP